

Delivery Requirements for Rollover® Flatbed Applicators

Truck Delivery

- The Rollover **CAN NOT** be offloaded using a liftgate due to its length.
- If there is a loading dock, the Rollover can be unloaded from the back of the truck.
- If there is no dock, a forklift **with long forks** is required for unloading.
- Please have customer confirm:
 - Forklift availability at delivery and uncrating (long forks)
 - Dry indoor storage area until installation
 - Clear truck access to the building

Forklift Requirement

- The Rollover is delivered in a large wooden crate: [Rollover Crate, Arrival](#)
- The crate must be disassembled, and the Rollover lifted from the center to remove the bottom pallet. Forklift with **long forks** is required for this process – **2,4 m / 8 ft**

Air Requirement

- Clean, dry, compressed air is required.
- **Minimum air pressure: 6 bar / 87 psi.**
- Compressor is not included with the Rollover.

Doorways

- Measure all doorways, hallways, and access points from delivery location to final installation area and ensure the Rollover can be turned where needed due to its length.
- Confirm there are no steps or obstacles
- The Rollover can be transported vertically using a Vertical Transport Device (VTD) if required.

Vertical Transport Device (VTD)

Rollover Flexi VTD

- Minimum doorway height: 5.9 ft (5' 10 55/64")
- Minimum doorway width: 2.95 ft (2' 11 7/16")
- Removing casters saves approx. 3.9"
- Video: [Rollover Flexi VTD Video](#)

Rollover Classic VTD

- Minimum doorway height: 6.5 ft (6'6")
- Minimum doorway width: 2.72 ft (2' 8 43/64")
- Removing casters saves approx. 3.9"
- Video: [Rollover Classic VTD Video](#)

Checklist – Delivery & Installation

Delivery & Access

- ☐ Delivery site accessible for truck delivery
- ☐ Loading dock available
- ☐ Forklift with long forks available (2,4m / 8 ft)
- ☐ Dry indoor storage area available
- ☐ Truck access clear

Installation Preparation

- ☐ Compressed air available (6 bar / 87 psi minimum)
- ☐ Wooden crate can be disassembled on site
- ☐ Installation area prepared and ready

Doorways & Transport Route

- ☐ All doorways measured
- ☐ All hallways/access routes checked and
- ☐ Rollover can be turned where required
- ☐ No steps or obstacles along route

Vertical Transport Device (If required)

- ☐ Vertical Transport Device required
- ☐ Door opening dimensions confirmed
- ☐ Classic VTD (Rental item 00031)
- ☐ Flexi VTD (Single-use item 10176)

Customer Acknowledgement

I confirm that the site is prepared for delivery and installation.

Date/Name: _____